

Audit Report

Station name: Pha Din, Vietnam 21°34'16''N 103°31'0''E
Date: July 4, 2016
Auditor: Prof. Dr. Alfred Wiedensohler (WMO-GAW-WCCAP,
TROPOS, Germany)
Responsible people: Mr. Günther Wehrle (PSI, Switzerland)

First of all, I would like to thank the people of the Vietnam Met Office in Hanoi and the people from the regional office for the great hospitality, hosting me for three days. Especially, I would like to thank Vang A. Phia (head of station) and Vang A. Tuang (deputy head of station). Furthermore, I would like to thank Valentin Graf from the Swiss Met Office and Günther Wehrle von PSI for their support here in Vietnam.



Group photo taken during the audit day July 4, 2016



Pha Din Station

General Conclusion:

The GAW station Pha Din is in a very good condition in terms of the aerosol measurement program.

General Comment:

PSI has set up together with the Vietnam Met Office a very good aerosol package, however, there are two issue, which have to be clarified.

1. The inlet configuration might not be optimum for cloud events.
2. The activity of the station personnel needs to be improved

More:

Manuals for instruments are not available on site. A digital logbook for all aerosol-related activities is available, however no logbook entries have been done by the station personnel. Last entries were done by PSI people in Nov. 2015.

Picture about the whole set-up are shown below:

| Time | User | Message |
|----------------------|--|---------|
| 2015-10-15T08:44:40Z | USER: hu, I am Long. Today, I visit Pha Din station to check the status. Every | |
| 2015-11-24T14:01:22Z | USER: zero filter check | |
| 2015-11-24T14:47:04Z | USER: changed filters before mass flow controller | |
| 2015-11-24T14:58:57Z | USER: mass flow filter change finished | |
| 2015-11-24T15:02:25Z | USER: started nephelometer full calibration | |
| 2015-11-24T15:02:42Z | USER: co2 flow 4 lpm, normal | |
| 2015-11-24T16:14:55Z | USER: neph calibration finished | |
| 2015-11-24T17:32:03Z | USER: Ende ZeroDatenaufnahme nach ester kalibration | |
| 2015-11-24T17:38:20Z | USER: Start full calibration, second after arrival and before cleaning | |
| 2015-11-24T19:19:03Z | USER: Zero filter applied after second calibration to measure stability | |
| 2015-11-24T19:19:24Z | USER: Pump piston replaced | |
| 2015-11-25T01:43:15Z | USER: com ports on the card case changed again after reboot | |
| 2015-11-25T05:07:51Z | USER: changed temp and rh sensor at inlet | |
| 2015-11-25T05:08:19Z | USER: cleaned neph, leak test ok, do full calibration | |
| 2015-11-25T05:59:53Z | USER: start one more neph calibration | |
| 2015-11-25T12:41:47Z | USER: first calibration started after firmware update | |
| 2015-11-25T16:30:21Z | USER: full calibration plus additional zero check finished | |
| 2015-11-25T16:30:37Z | USER: connected everything to ambient air | |
| 2015-11-26T09:10:36Z | USER: Full calibration Neuphometer | |
| 2015-11-26T09:36:02Z | USER: Total flow 7.272 | |
| 2015-11-26T09:48:50Z | USER: Flow Neeph 3.790 | |
| 2015-11-26T09:52:23Z | USER: Aethr 3.469 | |
| 2015-11-26T09:54:30Z | USER: Flow dilution air 3.506 | |
| 2015-11-26T10:21:26Z | USER: g.w. LED 1 Neph setting changed from 200 to 210 to make LED more br | |
| 2015-11-26T10:41:30Z | USER: zero check started | |
| 2015-11-26T12:13:53Z | USER: end of zero filter measurement | |
| 2015-11-26T13:34:10Z | USER: Zupdater | |
| 2016-04-10T18:22:54Z | USER: hello, phadin Pha thay bang loc | |

Logbook of the Pha Din station

| CATSOS aerosol monitoring station - PDI | | | | | | | | | |
|--|---------|-------|-------|-------|-----|-------|----------|----------|--|
| Current: 2016-07-04 04:13:31 | | | | | | | | | |
| Digital readings: nephelometer | | | | | | | | | |
| SC 890nm | (ng/m3) | 67.2 | 67.2 | 113.4 | 0.0 | 196.9 | 03:50:52 | 04:06:00 | |
| SC 890nm | (1/Mu) | 7.9 | 7.8 | 5.2 | 0.0 | 8.1 | 03:50:52 | 04:12:00 | |
| SC 890nm | (1/Mu) | 9.7 | 9.7 | 6.5 | 0.0 | 9.1 | 03:50:52 | 04:12:00 | |
| SC 890nm | (1/Mu) | 2.4 | 2.4 | 2.5 | 0.0 | 3.3 | 03:50:52 | 04:00:00 | |
| Digital readings: Nephelometer | | | | | | | | | |
| SC 890nm | (L/Mu) | 5.2 | 10.0 | 0.0 | 0.0 | 10.2 | 03:50:52 | 04:11:00 | |
| SC 890nm | (L/Mu) | 2.7 | 2.7 | 0.0 | 0.0 | 2.7 | 03:50:52 | 04:07:00 | |
| SC 890nm | (L/Mu) | 7.2 | 7.2 | 0.0 | 0.0 | 7.4 | 03:50:52 | 04:02:00 | |
| SC 890nm | (L/Mu) | 2.2 | 2.2 | 0.0 | 0.0 | 2.7 | 03:50:52 | 04:04:00 | |
| SC 890nm | (L/Mu) | 2.3 | 2.3 | 0.0 | 0.0 | 2.6 | 03:50:52 | 04:08:00 | |
| SC 890nm | (L/Mu) | 1.3 | 2.0 | 1.8 | 0.0 | 1.1 | 03:50:52 | 03:58:00 | |
| Alpha GR | (L/Mu) | 0.7 | 0.8 | 1.3 | 0.0 | 1.5 | 03:50:52 | 04:07:00 | |
| Alpha GR | (L/Mu) | 1.1 | 1.0 | 0.0 | 0.0 | 1.4 | 03:50:52 | 04:09:00 | |
| Neph P | (hPa) | 845.2 | 845.3 | 820.6 | 0.0 | 849.3 | 03:50:52 | 04:07:00 | |
| Neph T | (C) | 27.8 | 27.3 | 26.6 | 0.0 | 27.8 | 03:50:52 | 04:11:00 | |
| Neph RH | (%) | 34.0 | 33.3 | 32.8 | 0.0 | 34.9 | 03:50:52 | 03:59:00 | |
| Analog readings: Mass Flow Controller | | | | | | | | | |
| Flow Aeth | (vips) | 3.4 | 3.4 | 3.2 | 0.0 | 3.4 | 03:50:52 | 04:07:00 | |
| Flow Neph | (vips) | 3.8 | 3.8 | 3.8 | 0.0 | 3.8 | 03:50:52 | 04:00:00 | |
| Flow DilAir | (vips) | 3.5 | 3.5 | 3.5 | 0.0 | 3.5 | 03:50:52 | 04:11:00 | |
| Analog readings: Sensors | | | | | | | | | |
| P Mixed Air | (mbar) | 822.0 | 822.0 | 784.7 | 0.0 | 822.1 | 03:50:52 | 03:59:00 | |
| P Pump Air | (mbar) | 615.4 | 615.4 | 587.4 | 0.0 | 615.5 | 03:50:52 | 04:08:00 | |
| T Indoor | (C) | 24.5 | 24.5 | 23.3 | 0.0 | 24.6 | 03:50:52 | 03:59:00 | |
| T Mixed Air | (C) | 24.3 | 24.3 | 23.2 | 0.0 | 24.4 | 03:50:52 | 03:59:00 | |
| RH Mixed Air | (%) | 35.6 | 35.6 | 34.5 | 0.0 | 36.6 | 03:50:52 | 03:59:00 | |
| T Ambient | (C) | 19.8 | 19.8 | 19.1 | 0.0 | 20.2 | 03:50:52 | 03:59:00 | |
| RH Ambient | (%) | 38.3 | 38.3 | 33.5 | 0.0 | 38.4 | 03:50:52 | 04:10:00 | |
| T Dil Air | (C) | 25.6 | 25.6 | 24.4 | 0.0 | 25.7 | 03:50:52 | 03:59:00 | |
| RH Dil Air | (%) | 0.4 | 0.4 | 0.3 | 0.0 | 0.4 | 03:50:52 | 04:12:00 | |
| Analog readings: Aethalometer and Nephelometer | | | | | | | | | |
| SC 890nm | (ng/m3) | 67.2 | 67.2 | 113.4 | 0.0 | 196.9 | 03:50:52 | 04:06:00 | |
| SC 890nm | (1/Mu) | 7.9 | 7.8 | 5.2 | 0.0 | 8.1 | 03:50:52 | 04:12:00 | |
| SC 890nm | (1/Mu) | 9.7 | 9.7 | 6.5 | 0.0 | 9.1 | 03:50:52 | 04:12:00 | |
| SC 890nm | (1/Mu) | 2.4 | 2.4 | 2.5 | 0.0 | 3.3 | 03:50:52 | 04:00:00 | |
| UTC: 2016-07-04 04:13:31 186.17606 | | | | | | | | | |

Current measurements of the Pha Din station



Indoor aerosol splitter and T/RH sensor of the aerosol set-up



Aerosol set-up

Audit Recommendations:

- The manuals of the instruments must be available at the station.
- We suggest strongly that the station personnel follows the operation procedures written by PSI and use the logbook.

Reference flow meter:

Type of reference flow meter: The mini-BUCK Calibrator (electronic bubble flow meter)

Serial number: A30441

Last calibrated: 2013

Audit recommendations:

No further recommendation

Aerosol inlet:

| | |
|-----------------------------|--|
| Inlet: | TSP |
| Material: | conductive tubing (last 1.5m), rest copper line |
| Vertical: | 10 m |
| Horizontal: | 1.5 m |
| Bends | 1 |
| Inlet tube: | Outer diameter: 12 mm Inner diameter: 10 mm |
| Flow rate: | 10.7 l/min |
| Calculated Reynolds number: | 1216 → ok |
| Aerosol drying by dilution: | standard: 7.2 l/min ambient + 3.5 l/min dry air, dry air added 10cm downstream of inlet head |

Present condition:

| | |
|---------------------|-----------|
| Indoor aerosol RH: | 35% |
| T ambient: | 19.2°C |
| RH ambient: | 99% |
| Dew point T: | 19.2°C |
| Dilution flow rate: | 3.7 l/min |


Inlet Configuration:




Pha Din aerosol inlet mast




Actual TSP inlet, showing the insect screen




Time series of the wind speed (6 h resolution) at the Pha Din station in 2015



Time series outdoor & indoor temperature Pha Din station



Time series outdoor & relative humidity of the mixed aerosol flow measured in the aerosol splitter in side of Pha Din station



Time series dew point temperature Pha Din station

Comments:

The station is according to the Mr. Günther Wehrle and Dr. Nicolas Bukowiecki (PSI) frequently in cloud. The CATCOS team of PSI decided during planning phase in 2011 that a TSP inlet should be used. In the WMO-GAW report following is recommended:

„Sampling sites that are frequently in clouds or fog (e.g. mountain sites) should use whole air inlets to sample cloud or fog droplets as well as aerosols. This air should be dried rapidly to avoid inertial particle losses.”

The TSP inlets probably works as a whole air inlets, although no heated inlet is employed. The wind velocity seems never to exceed 10 m/s over all seasons, meaning that the stopping distance is never larger than 3 cm in the worst case, even for a 20 μ m droplet (stopping distance = 3x relaxation time x wind velocity). The droplets would make it into the sampling cone, which is 6 cm in diameter at the top.

Another problem might be caused by the insect screen with about 50% porosity, which may cause impacts of cloud droplets. The effect on aerosol particle properties such as the particle light scattering and absorption coefficients is difficult to estimate. It might be that a part of the cloud droplet are not taken into the dilution flow. The consequence might be that that the particle light scattering and absorption coefficients are measured too low during cloud periods. Since there is no independent cloud detector or particle number size spectrometer, data cannot be flagged for the cloud periods.

Looking at the time series of T, RH and T_{dew}, there was a problem with the RH/T sensor at the TSP inlet until fall 2015. Additionally, there was a technical failure of the compressor, leading to high aerosol relative humidity inside of the instruments. This seems to have been solved after the visit of PSI people in fall 2015. The data afterwards seem to be reliable.

Coming back to cloud problem, the RH sensor at the inlet can be used to identify the period of cloud events. PSI should estimate the effect on a possible change of the aerosol particle parameters by looking at the data before and after cloud events (excluding time periods in this analysis when there was precipitation)

Audit Recommendation:

- The inlet configuration might be not optimum due to the insect screen. Data should be checked for cloud events and possible be flagged, if the aerosol particle properties are influenced.
- As a minor issue, I suggest to change possibly the copper tubing to stainless steel at the lower end of the mast.

Particle light absorption coefficient:

| | |
|---|---|
| Instrument: | Filter-based absorption photometer |
| Type: | Aethalometer AE31 |
| Serial number: | 1145 |
| Wavelengths: | 370, 450, 571, 615, 660, 880 and 950 nm |
| Firmware version: | 985d8 |
| Data format: | dataline |
| Last calibrated: | before installation at PSI, no information presently |
| By: | PSI people |
| Nominal flow rate: | 3.4 l/min |
| Measured flow rate at 822 hPa, 24°C: | 3.6 l/min |
| Flow rate indicated on front panel: | 3.4 l/min |
| Indicated concentration with absolute filter: | 0.0 g/m ³ |
| Nominal filter change: | 60% transmission → ok |
| Condition of instrument: | visually, the instrument is an excellent condition |
| Data submitted to data centre: | Data are submitted by PSI people to the WDCA, according to PSI. Please check the data for the time periods of high instrument RH |

Audit Recommendation:

No further recommendation

Particle light scattering coefficient:

| | |
|---|------------------------------|
| Instrument: | Integrating nephelometer |
| Type: | Ecotech Aurora 3000 |
| Serial number: | 12-0248 (built in 2012) |
| Wavelengths: | 635, 525, 450 nm |
| Firmware version: | Version 1.14 |
| Gases for span check: | CO ₂ |
| Last zero check: | every 36 h (zero adjustment) |
| Last span check: | Nov. 2015 |
| By: | Mr. Günther Wehrle |
| Nominal flow rate: | 3.8 l/min |
| Measured flow rate: | 3.9 l/min at 822 hPa, 24°C |
| Indicated concentration with absolute filter: | 0.0 Mm ⁻¹ |

Condition of instrument: Visually, the instrument seems to be in an excellent condition

Data submitted to data centre: Yes, data are submitted by PSI people to the WDCA (HYMENET is being trained to handle the submission in the future), according to PSI. Please check if the data for the time periods of high indoor RH

Comments:

The instrument was not calibrated with CO₂ by the station personnel since the last visit of PSI people in Nov. 2015. The recommended calibration frequency should not be longer than 3 month, which is also given in the operation procedure written by PSI.

The station personnel did not do a calibration during the audit. According to PSI, the station personnel has performed a calibration directly after the audit.

Audit Recommendation:

- The station personnel must perform the CO₂ calibration for the integrating nephelometer every three month.
- The system needs to be changed to a daily Zero Check
- The aerosol flow should be measured frequently and the values should be also written into the logbook.